

No: ITBP/SHQ (Delhi)/Engr/E-Tender/2024- 135
 Sector Head quarter (Delhi)
 Indo-Tibetan Border Police Force
 Ministry of Home Affairs, Govt. of India
 PO- Madangir, New Delhi-110062

Date:- 10/12/24

Notice Inviting limited Tender

Sealed Notice Inviting Quotations are invited by undersigned on behalf of management of ITBP Public School, for following work from the approved and eligible firms/contractors of CPWD, MES, Railway, BRO, and State PWD and other specialized in water proofing of UG Tank etc. for the work of "Water Proofing for lift duct reverse side at ITBP Public School Dwarka, New Delhi". The Percentage rate quotation should reach this office on or before 26.12.24 up to 1600 Hrs. and same will be opened on next day at 1600 Hrs. in the presence of contractor whoever wish to present.

Name of Work:- Water Proofing for lift duct reverse side at ITBP Public School Dwarka, New Delhi.

Note:- The quotation shall be obtained from Office of the DIG SHQ Delhi, ITBP Tigri camp, Pin-110062 on all working days up to 26.12.24 at 1200 Hrs.

S.N	Description of item	Unit	Qty	Rate	Amt
1	Dismantling dressed stone work ashlar face stone work, marble work or precast concrete work manually/ by mechanical means including stacking of serviceable and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge.	cum	0.72	2877.75	2071.98
2	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer-in-charge.	cum	5.76	2434.25	14021.28
3	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-charge.	cum	60.48	177.50	10735.20
4	Providing & Applying polymer modified, flexible cementitious negative side waterproofing coating with elastic waterproofing polymers on interior wall plaster surface in three coats @14.35 kg /10 sqm. one coat of self priming of cementitious waterproofing polymer (dilution with water in the ratio of 1:1) and two coats of cementitious waterproofing polymer (dilution with water in the ratio of 3:1) after scrapping and properly cleaning the surface to remove pre-existing paint film & loose particles till plaster is visible, complete in all respect as per the direction of Engineer-in-Charge.	sqm	80.40	447.35	35966.94

[Handwritten signature]

5	Providing and applying crystalline mortar by mixing in the ratio of 4.5 : 1 (4.5 parts crystalline mortar : 1 part water) for the treatment of faulty construction joints, cracks, tie rod holes and spalled & honeycombed surface of RCC underground structures like basement, water tanks, bridge deck etc. to ensure water tightness. The crystalline mortar shall conform to the EN 1504-3 having compressive strength Class R4 245 MPa and adhesive bond strength Class R3 21.5 MPa. The work shall be carried out all complete as per specification and the direction of the engineer-in-charge. The product performance shall carry guarantee for 10 years against any leakage. For sealing cracks and faulty construction joints, routed out/making U-shape groove size 25x25mm and then primed the area with integral crystalline slurry @0.05kg/running metre and while the surface is tacky filled the groove upto surface with crystalline mortar @1.50kg/ running metre. Once crystalline mortar is touch dry then finally applied two coats of integral crystalline slurry @0.05kg/running metre per coat	Mtr	30.00	547.70	16431.00
6	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and lift upto 1.5m.	cum	57.60	196.00	11289.60
7	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering. - All work up to plinth 1:4:8 (1 Cement : 4 coarse sand (zone-III) derived from natural sources ; 8 graded stone aggregate 40 mm nominal size derived from natural sources)	cum	5.76	6812.00	39237.12
8	Marble stone flooring with 18 mm thick marble stone, as per sample of marble approved by Engineer-in-charge, over 20 mm (average) thick base of cement mortar 1:4 (1 cement : 4 coarse sand) laid and jointed with grey cement slurry, including rubbing and polishing complete with : Udaipur green marble	sqm	35.00	2510.40	87864.00
Total=					217617.00
Quoted % ge above or below=					
Quoted Amount in Figure=					

General Conditions:-

1. The work shall be carried out as per CPWD specification and as directed by the Engineer-in-Charge.
2. The undersigned reserves all rights to accept or reject any or all quotation or alter the quantity for work order without assigning any reason.
3. Payment shall be made as per quoted rate, which shall be inclusive of all taxes, IT, GST etc. and no extra payment on any account will be entertained.

4. Period of completion is 03 (three) months from the date of issue of work order.
5. The successful quotationers shall be governed by labour contract rules and regulations.
6. Scanned copy of valid registration certificate of firms/specialized agency,
7. Water proofing work shall have at least on year warranty against seepage/ cracks or any damages.


Second-in-Command (Engr)

SHQ (DELHI) ITB Police


For and on behalf of Hon'ble President of India

- Copy to:
1. DIG (G&W) Dte Gen, ITB Police for information.
 2. IT Cell, NW Ftr with request for uploading tender notice at ITBP website.
 3. Principal, ITBP Public school, Dwarka for info and vide publicity.
 4. Notice board- SHQ Delhi, 28th Bn, 39th Bn & 42nd Bn ITBP.
 5. Vinrant Enterprises, B-1015, Sector B, Greenfield, Faridabad, Haryana.
 6. M/S Associated Traders, 42 Central Market, Dakshin Puri, New Delhi-110062.
 7. S.K.Builders, C-47, Gali no.- 07, North Ghonda, North East Delhi 110053.
 8. Bhupinder singh, 12/15 top floor near som bazar, Ashok Nagar West Delhi-110018.
 9. Sonali Water proofing solution Rz 9/47, Gali No. 12, Tughlakabad Extension, Delhi.

