

Schedule of Quantities

S.No.	Description of Item / Work	Qty.	Unit	Rate in figures in Rupees	Amount in Rupees
1	Drilling bore hole including conducting SPT, sample collection at 1.5 Mtr interval in hilly terrain and every change of strata along with undisturbed sample collection at 1.5,3.0,4.5 and 6 Mtr upto 15 mtr and so on at interval of every 1.5 Mtr and on change of strata and carrying out other related tests for carrying out safe bearing capacity of soil including, mobilization and demobilization of tools, machinery and man power including marking of bore hole location on ground as per direction of Engineer-in-charge. Preparation and submission of hard copies and soft copy in Pdf format of the final report of all the test / field investigation/ laboratory test carried as detailed in specification inclusive of bore loads and recommendation of the parameter found out from the tests including safe bearing capacity for various foundation sizes and at various depth such as 1.5m, 2.0m, 3.0m, 4.00 Mtr.	02	No. of Bores		
Total (in words):-					

Sobodh.

25/07/22

Commandant (Engr)

श्री०मु० (तेजपुर) भा०लि०सी० पुलिस बल
SMQ (Tezpur) I.T.B. Police Force